

5581 SW 50<sup>th</sup> St. - Kingman, KS 67068 800-301-3487 \* (620) 532-3487 Fax: (620) 532-1125

www.nevillebuilt.com email: info@nevillebuilt.com

## Dump Trailers



Neville Built full frame steel end dump trailers are available for your hauling needs. We offer a variety of sidewall height options in lengths of 24', 26' and 28'. Standard suspension is spring, however, air-ride or air-ride lift axles are available. We also offer a variety of tarp systems.



## **Standard Specifications:**

- > 50,000 PSI minimum yield strength steel body (10 gauge sidewall and 3/6 floor)
- ➤ Muncie 5-stage hoist
- > Grote sealed wiring system with rubber mounted LED lights
- > 25,000# rated axles
- > 9700 Hutch spring suspension (Ridewell air-ride option)
- Jost 2-speed heavy duty landing legs
- > Tail gate chains